

令和5年度

上水道管布設工事（1工区）

数量計算書

箕輪町 木下

数量計算書						
コード	名称	形状寸法		単位	数量	備考
		町道As φ75 DP=0.9				
			L = 105.0 m			
			105.0 × 2 = 210.00	m	210.0	
	アスファルト切断工	t=10cm以下				
		BH0.28m ³	105.0 × 3.0 = 315.00	m ²	315.0	
	舗装版取壊し積込み	t=10cm以下				
		掘削積込	0.60 × 1.09 × 105.0 = 68.67	m ³	69.0	
	機械掘削工	BH0.28m ³				
			0.60 × 0.39 × 105.0 = 24.57	m ³	25.0	
	砂入替工	保護砂				
		発生土	0.60 × 0.31 × 105.0 = 19.53	m ³	20.0	
	機械埋戻工	BH0.28m ³				
		RC-40~0	0.60 × 105.0 = 63.00	m ²	63.0	
	下層路盤工	t = 25cm				
		M-25	0.60 × 105.0 = 63.00	m ²	63.0	
	上層路盤工	t = 10cm				
		再生密粒度As20F	315.0	m ²	315.0	
	表層工	t=4cm 幅1.4以上				
		BH0.28m ³ 土砂	69.00 - 20.00 = 49.00	m ³	49.0	
	残土処理工	4t-2km				
		BH0.28m ³ As	315.00 × 0.04 = 12.60	m ³	13.0	
	アスファルト運搬工	2t-9.8km				
			13.00	m ³	13.0	
	アスファルト処分費					
		M-25	315.00 - 63.00 = 252.00	m ²	252.0	
	不陸整正工	t=5cm 幅1.8以上				