

数量総括表

上段:当初数量

下段:変更後数量

No.1

| 工種               | 細目                        | 計算式                 | 数量     | 単位             |
|------------------|---------------------------|---------------------|--------|----------------|
| 道路改良工            |                           |                     |        |                |
| 道路土工<br>構造物撤去取壊工 |                           |                     |        |                |
|                  | 舗装切断 t=5cm                | 構造物撤去工数量表参照 =4.8    | 5.00   | m              |
|                  | 舗装版撤去積込 t=5cm             | 構造物撤去工数量表参照 =188.8  | 189.00 | m <sup>2</sup> |
|                  | 廃材運搬 As塊 L=7.0km<br>南重想定  | 188.8*0.05 =9.44    | 9.00   | m <sup>3</sup> |
|                  | 石積撤去                      | 構造物撤去工数量表参照 =6.56   | 7.00   | m <sup>2</sup> |
|                  | コンクリート取壊し<br>二次製品         | 構造物撤去工数量表参照 =1.02   | 1.00   | m <sup>3</sup> |
|                  | 廃材運搬 二次製品 L=7.0km<br>南重想定 | =1.0                | 1.00   | m <sup>3</sup> |
|                  |                           |                     |        |                |
| 処分費              |                           |                     |        |                |
|                  | 廃材処理<br>As塊               | 9.44*2.3/1.8 =12.06 | 12.10  | m <sup>3</sup> |
|                  | 廃材処理<br>二次製品              | 1.02*2.5/1.8 =1.42  | 1.40   | m <sup>3</sup> |
|                  |                           |                     |        |                |
| 土工               |                           |                     |        |                |
|                  | 機械掘削                      | 作業土工数量表参照 =76.2     | 76.00  | m <sup>3</sup> |
|                  | 埋戻し 締固め<br>良質発生土          | 作業土工数量表参照 =23.1     | 23.00  | m <sup>3</sup> |
|                  | 残土運搬 L=2km<br>任意箇所へ       | 作業土工数量表参照 =50.5     | 51.00  | m <sup>3</sup> |
|                  | 残土受入地整地                   | =50.5               | 51.00  | m <sup>3</sup> |
|                  | 基面整正<br>側溝部               | 作業土工数量表参照 =47.8     | 48.00  | m <sup>2</sup> |
|                  |                           |                     |        |                |
| 小型水路工<br>側溝工     |                           |                     |        |                |
|                  | 自由勾配側溝 300×300<br>防音型     | 水路工数量表参照 =71.3      | 71.30  | m              |







## 埋 戻 土量計算書

PAGE1-1

| 測 点               | 距 離   | 断 面 積 | 平均断面積 | 土 量   | 摘 要 |
|-------------------|-------|-------|-------|-------|-----|
| 側溝分<br>EC. 1-4.0m |       | 0.1   |       |       |     |
| EC. 1             | 4.00  | 0.1   | 0.10  | 0.4   |     |
|                   |       |       |       |       |     |
| EC. 1             | 6.70  | 0.2   | ----- | ----- |     |
| P20.000           | 1.58  | 0.1   | 0.15  | 0.2   |     |
| P30.000           | 10.00 | 0.3   | 0.20  | 2.0   |     |
| P40.000           | 10.00 | 0.3   | 0.30  | 3.0   |     |
| BC. 2             | 7.92  | 0.4   | 0.35  | 2.8   |     |
| SP. 2             | 10.49 | 0.3   | 0.35  | 3.7   |     |
| P60.000           | 1.58  | 0.4   | 0.35  | 0.6   |     |
| EC. 2             | 8.91  | 0.4   | 0.40  | 3.6   |     |
| BC. 3             | 2.49  | 0.4   | 0.40  | 1.0   |     |
| SP. 3             | 8.33  | 0.4   | 0.40  | 3.3   |     |
| EC. 3             | 8.33  | 0.3   | 0.35  | 2.9   |     |
|                   |       |       |       |       |     |
| 先行工事<br>側溝設置分控除   |       |       |       |       |     |
| EC. 3             | 0.00  | -0.2  | ----- |       |     |
| EC. 3-2.0m        | 2.00  | -0.2  | -0.20 | -0.4  |     |
|                   |       |       |       |       |     |
|                   |       |       |       |       |     |
|                   |       |       |       |       |     |
|                   |       |       |       |       |     |
|                   |       |       |       |       |     |
|                   |       |       |       |       |     |
|                   |       |       |       |       |     |
|                   |       |       |       |       |     |
|                   |       |       |       |       |     |
|                   |       |       |       |       |     |
|                   |       |       |       |       |     |
|                   |       |       |       |       |     |
|                   |       |       | 合 計   | 23.1  | m3  |



表層工 面積計算書

PAGE3-1

| 測 点     | 距 離   | 幅    | 平均幅  | 面積    | 摘 要 |
|---------|-------|------|------|-------|-----|
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
| EC. 1   | 6.70  | 2.44 | 1.22 | 8.2   |     |
| P20.000 | 1.58  | 2.40 | 2.42 | 3.8   |     |
| P30.000 | 10.00 | 2.86 | 2.63 | 26.3  |     |
| P40.000 | 10.00 | 2.96 | 2.91 | 29.1  |     |
| BC. 2   | 7.92  | 3.16 | 3.06 | 24.2  |     |
| SP. 2   | 10.49 | 2.73 | 2.95 | 30.9  |     |
| P60.000 | 1.58  | 2.70 | 2.72 | 4.3   |     |
| EC. 2   | 8.91  | 3.46 | 3.08 | 27.4  |     |
| BC. 3   | 2.49  | 3.56 | 3.51 | 8.7   |     |
| SP. 3   | 8.33  | 3.58 | 3.57 | 29.7  |     |
| EC. 3   | 8.33  | 3.51 | 3.55 | 29.6  |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      |      |       |     |
|         |       |      | 合 計  | 222.2 | m2  |





下層路盤工 面積計算書

| 測 点     | 距 離   | 幅    | 平均幅   | 面積    | 摘 要 |
|---------|-------|------|-------|-------|-----|
| P20.000 | 0.00  | 0.43 | ----- | ----- |     |
| P30.000 | 10.00 | 0.43 | 0.43  | 4.3   |     |
| P40.000 | 10.00 | 0.43 | 0.43  | 4.3   |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      |       |       |     |
|         |       |      | 合 計   | 8.6   | m2  |



水路工 数量表

1式当り(1-1)

| 名 称               | 規 格                     | 単 位 | 数 量  | 摘 要   |
|-------------------|-------------------------|-----|------|-------|
| 自由勾配側溝            | 防音型<br>300×300          | m   | 71.3 | 71.30 |
|                   |                         |     |      |       |
| 自由勾配側溝<br>C o 蓋   | 防音型 車道用<br>300型 L=0.5m  | 枚   | 57.0 | 57.00 |
| 自由勾配側溝<br>グレーチング蓋 | 防音型 T-20<br>300型 L=1.0m | 枚   | 7.0  | 5.00  |
|                   |                         |     |      |       |
|                   |                         |     |      |       |
|                   |                         |     |      |       |
|                   |                         |     |      |       |
|                   |                         |     |      |       |
|                   |                         |     |      |       |
|                   |                         |     |      |       |
|                   |                         |     |      |       |
|                   |                         |     |      |       |
|                   |                         |     |      |       |
|                   |                         |     |      |       |
|                   |                         |     |      |       |
|                   |                         |     |      |       |
|                   |                         |     |      |       |





| 構造物撤去工 数量計算書 |                                     | 1式当り           | 1-1 |
|--------------|-------------------------------------|----------------|-----|
| 名 称          | 計 算                                 | 単 位            | 数 量 |
| 構造物取壊し工      |                                     |                |     |
| 舗装版切断        | L= 2.6 (EC. 3) = 2.6                |                |     |
|              | L= 2.2 (EC. 1) = 2.2                | m              |     |
|              | $\Sigma A = 4.80$                   | m              | 4.8 |
|              |                                     |                |     |
|              |                                     |                |     |
|              |                                     |                |     |
|              |                                     |                |     |
|              |                                     |                |     |
| 舗装版撤去        |                                     |                |     |
|              | 別紙計算書より                             |                |     |
|              | A1= 188.80 = 188.80                 |                |     |
|              |                                     |                |     |
|              | $\Sigma A = 188.80$                 | m <sup>2</sup> | 189 |
|              |                                     |                |     |
|              |                                     |                |     |
|              |                                     |                |     |
|              |                                     |                |     |
|              |                                     |                |     |
|              |                                     |                |     |
|              | 石積撤去 (L=6.9, P20.00付近)              |                |     |
|              | A= 0.95m×6.9m = 6.56                | m <sup>2</sup> | 6.6 |
| 排水構造物撤去工     |                                     |                |     |
|              | 既設水路BF250撤去                         |                |     |
|              | V= 0.024m <sup>2</sup> ×42.3 = 1.02 | m <sup>3</sup> | 1.0 |
|              |                                     |                |     |
|              |                                     |                |     |
|              |                                     |                |     |

| 測 点     | 距 離   | 幅   | 平均幅   | 面積    | 摘 要 |
|---------|-------|-----|-------|-------|-----|
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
| EC. 1   | 6.70  | 2.3 | ----- | ----- |     |
| P20.000 | 1.58  | 2.0 | 2.15  | 3.4   |     |
| P30.000 | 10.00 | 2.5 | 2.25  | 22.5  |     |
| P40.000 | 10.00 | 2.6 | 2.55  | 25.5  |     |
| BC. 2   | 7.92  | 2.7 | 2.65  | 21.0  |     |
| SP. 2   | 10.49 | 2.8 | 2.75  | 28.8  |     |
| P60.000 | 1.58  | 2.6 | 2.70  | 4.3   |     |
| EC. 2   | 8.91  | 3.0 | 2.80  | 24.9  |     |
| BC. 3   | 2.49  | 3.1 | 3.05  | 7.6   |     |
| SP. 3   | 8.33  | 3.0 | 3.05  | 25.4  |     |
| EC. 3   | 8.33  | 3.1 | 3.05  | 25.4  |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     |       |       |     |
|         |       |     | 合 計   | 188.8 | m2  |